April 2022 Update Pack

Dear Colleague,

Thank you for downloading this April update, the first of 2022.

This update brings one specification change, in that the spandrels used in conjunction with E-WM-31 can now be lined with a single layer of Fermacell as an alternative to the 2 layers of gypsum board.

There are also a number of product name changes also made: Elecoframe's E-WT-3 is now manufactured under the Openwall name, and two flanking conditions in Appendix A2 are also being produced under different names: Stewart Milne Timber Systems Sigma[®] Roof Spandrel Panel System now comes from Donaldson Timber Systems; and **NYT**ROOF *RAPID FIT SYSTEM* has been rebranded and is provided by **NTS**ROOF.

And additionally, we have restructured the text relating to putty pads in the light-frame walls to give added clarity on their purpose.

Please update your October 2021, 4th Edition Handbook as follows:

- 1. Remove and replace pages 3/4 and 9/10 of the Introduction.
- 2. Remove and replace page 5/6 of E-WM-31.
- 3. Remove and replace page 7/8 of E-WT-1.
- 4. Remove and replace page 7/8 of E-WT-2.
- 5. Remove and replace all pages of E-WT-3.
- 6. Remove and replace page 5/6 of E-WT-4.
- 7. Remove and replace page 5/6 of E-WS-1.
- 8. Remove and replace **page 7/8** of E-WS-2.
- 9. Remove and replace page 9/10 of E-WS-5.
- 10. Remove and replace **pages 1/2 and 9/10** of Appendix A2.

Yours sincerely

The offer

John Thompson Chief Executive, Robust Details Limited



Changes to the fourth edition following April 2022 update

Section	Page	Amendment	Section
Introduction	on		Separatir
Table 1	4	E-WT-3 renamed as Openwall prefabricated panels.	E-WS-1
Table 6a	9	NYTROOF RAPID FIT SYSTEM renamed NTSROOF RAPID FIT SYSTEM.	Services
		Stewart Milne Sigma [®] Panel renamed Donaldson Timber Systems Single Leaf Spandrel.	E-WS-2 Services
	10	NTS ROOF <i>RAPID FIT SYSTEM</i> added with applicable combinations.	E-WS-5
		Stewart Milne Sigma [®] Panel renamed Donaldson Timber Systems Single Leaf Spandrel.	Services
Separating	g Wa	all – Masonry	Appendix
E-WM-31			Contents
Spandrels	5-6	Note added regarding the linings for the spandrels panels	
Separatin	q Wa	all – Timber	
E-WT-1	•		Donaldson
Services	10	Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.	timber spand
E-WT-2			RAPID FIT
Services	7	Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.	SYSTEM
E-WT-3			
Bullet points	1	1st point amended to new company name of Openwall.	
Isometric	1	Timber battens introduced to break continuity of rigid insulation.	
Frame construction	1	Identification label amended to new company name of Openwall.	
Flanking wall junctions	2	Timber battens introduced to break continuity of rigid insulation.	
Services	6	Note added referencing putty pads and other proprietary liners.	
Checklist	8	Name changed to Openwall on first check item.	
		Contact details amended.	
E-WT-4			
Services	6	Text reordered to clarify putty pads	

Services 6 Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.

Section	Page	Amendment						
Separating Wall – Steel								
E-WS-1								
Services	6	Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.						
E-WS-2								
Services	6	Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.						
E-WS-5								
Services	10	Text reordered to clarify putty pads are an alternative to just the 2 layers of gypsum board.						
Appendix A	12							
Contents	1	Stewart Milne Timber Systems Sigma [®] Roof renamed Donaldson Timber Systems Single Leaf.						
		NYTROOF RAPID FIT SYSTEM renamed NTSROOF RAPID FIT SYSTEM.						
Donaldson timber spandrel	9	Stewart Milne Timber Systems Sigma [®] Roof renamed Donaldson Timber Systems Single Leaf.						
		Contact details amended.						
RAPID FIT SYSTEM	10	Heading amended to include name changed to NTS ROOF; and reference to timber walls.						
		Diagram 1 amended to show guidance for use on timber frame walls.						
		Diagram 2 amended to show joist positions.						
		Contact details amended.						

List of Robust Details

Table 1 – Separating walls

E-WM-1	masonry – dense aggregate blockwork (wet plaster)
E-WM-2	masonry – lightweight aggregate blockwork (wet plaster)
E-WM-3	masonry – dense aggregate blockwork (render and gypsum-based board)
E-WM-4	masonry – lightweight aggregate blockwork (render and gypsum-based board)
E-WM-5	masonry – Besblock "Star Performer" cellular blockwork (render and gypsum-based board)
E-WM-6	masonry – aircrete blockwork (render and gypsum-based board)
E-WM-7	Suspended from further registrations
E-WM-8	masonry – lightweight aggregate blockwork Saint Gobain – Isover RD35 (gypsum-based board)
E-WM-9	masonry – solid dense aggregate blockwork (render and gypsum-based board)
E-WM-10	masonry - aircrete thin joint blockwork with specified wall ties (render and gypsum-based board finish)
E-WM-11	masonry - lightweight aggregate blockwork (render and gypsum-based board) 100mm minimum cavity
E-WM-12	masonry - Plasmor "Aglite Ultima" lightweight aggregate blockwork (render and gypsum-based board)
E-WM-13	masonry - aircrete thin joint - untied blockwork (render and gypsum-based board)
E-WM-14	masonry – lightweight aggregate blockwork Saint Gobain – Isover RD35 (gypsum-based board) with 100mm minimum cavity
E-WM-15	masonry – aircrete blockwork Saint Gobain - Isover RD35 (gypsum-based board)
E-WM-16	masonry - dense aggregate blockwork (render and gypsum-based board) with 100mm minimum cavity
E-WM-17	masonry – lightweight aggregate blockwork Saint Gobain-Isover RD Party Wall Roll (gypsum-based board)
E-WM-18	masonry – dense aggregate blockwork (wet plaster) with 100mm minimum cavity
E-WM-19	masonry – dense or lightweight aggregate blockwork (render and gypsum-based board) with 100mm minimum cavity and MONARFLOOR® BRIDGESTOP® system
E-WM-20	masonry – lightweight aggregate blockwork Saint Gobain – Isover RD Party Wall Roll (gypsum-based board) with 100mm minimum cavity
E-WM-21	masonry – lightweight aggregate blockwork (wet plaster) with 100mm minimum cavity
E-WM-22	masonry – lightweight aggregate blockwork – Knauf Earthwool Masonry Party Wall Slab or Superglass Party Wall Roll or URSA Cavity Batt 35 or URSA PARTY WALL ROLL (gypsum-based board) with 100mm minimum cavity
E-WM-23	masonry – aircrete blockwork Superglass Party Wall Roll (gypsum-based board) 100mm min cavity
E-WM-24	masonry – aircrete blockwork Saint Gobain – Isover RD Party Wall Roll (gypsum-based board) with 100mm minimum cavity
E-WM-25	masonry – Porotherm clay blockwork (Ecoparge and gypsum-based board) with 100mm minimum insulated cavity
E-WM-26	masonry – Besblock "Star Performer" cellular blockwork (gypsum-based board) with 100mm minimum insulated cavity
E-WM-27	masonry – lightweight aggregate blockwork Superglass Party Wall Roll (gypsum-based board) with minimum 75mm cavity
E-WM-28	masonry – lightweight aggregate blockwork Knauf Supafil [®] Party Wall (gypsum-based board) with minimum 100mm cavity
E-WM-29	masonry – Porotherm clay blockwork (Ecoparge and gypsum-based board) with 75mm minimum insulated cavity
E-WM-30	masonry – aircrete blockwork Knauf Supafil® Party Wall (gypsum-based board) with 100mm min cavity
E-WM-31	masonry – H+H – Celcon Elements (gypsum-based board) with 100mm minimum insulated cavity
E-WM-32	masonry – lightweight aggregate blockwork Knauf Earthwool Masonry Party Wall Slab (gypsum-based board) with minimum 75mm cavity
E-WM-33	masonry – lightweight aggregate blockwork Superglass Superwhite 34 (gypsum-based board) with 100mm minimum cavity
E-WM-34	masonry – Plasmor "Aglite Ultima' lightweight aggregate blockwork (render and gypsum-based board) with full-fill cavity insulation

See over for timber and steel frame walls

Introduction

List of Robust Details

Table 1 (continued) – Separating walls

E-WT-1	timber frame – without sheathing board
E-WT-2	timber frame - with sheathing board
E-WT-3	timber frame – Openwall prefabricated panels
E-WT-4	timber frame - Excel Industries Warmcell 500 insulation - with sheathing board
E-WS-1	steel frame – twin metal frame
E-WS-2	steel frame – British Gypsum Gypwall QUIET IWL
E-WS-3	steel frame – modular steel frame housing
E-WS-4	steel frame – twin metal frame - 250mm between linings
E-WS-5	steel frame – twin metal frame

		BRIDGESTOP® system	Smartroof system	Wall Cap RDA2	RoofSpace I-Roof	Space4 system	Donaldson Timber Single Leaf Spandrel	NTSROOF RAPID FIT SYSTEM	Nu-Span Spantherm
	E-WM-1	~		~		✓		~	~
walls	E-WM-2	~		~		~		~	~
	E-WM-3	~	~	~	v	✓		~	~
	E-WM-4	~	~	~	~	✓		~	~
	E-WM-5	~	~	~	~	✓		~	~
	E-WM-6		~	~	~				~
	E-WM-8	~	~	~	~	✓		~	~
	E-WM-9								
	E-WM-10		~	~	~				~
	E-WM-11	~	~	~	~	✓		~	~
	E-WM-12	~	~	~	~	✓		~	~
	E-WM-13		~	~	✓				~
	E-WM-14	~	~	~	~	✓		~	~
	E-WM-15		~	~	✓				~
	E-WM-16	~	~	~	✓	✓		~	~
	E-WM-17	~	~	✓	✓	✓		~	~
	E-WM-18	~		~		✓		~	~
	E-WM-19	✓ see note 1				✓		~	
	E-WM-20	~	~	~	v	✓		~	~
	E-WM-21	~		~		✓		~	~
	E-WM-22	~	~	~	~	✓		~	~
	E-WM-23	✓ see note 1	~	~	~				~
	E-WM-24	✓ see note 1	~	~	✓				~
	E-WM-25			~					~
	E-WM-26	~	~	~	✓	✓		✓	~
	E-WM-27	~	~	✓	✓	✓		v	v
	E-WM-28	~	✓	~	v	✓		✓	~
	E-WM-29			~					~
	E-WM-30	✓ see note 1	~	~	✓				~
	E-WM-31		✓	~	✓				~
	E-WM-32	~	✓	~	✓	✓		✓	~
	E-WM-33	~	~	~	~	~		~	~
	E-WM-34	v	~	~	~	~		~	v

Table 6a - Robust Detail separating walls which can be used together with the specific flanking constructions contained in Appendix A2

Key

 When constructing these walls off raft foundations, the raft must have insitu concrete with 150mm minimum thickness.


See over for timber and steel frame walls

Introduction


Table 6a (continued) – Robust Detail separating walls which can be used together with the specific flanking constructions contained in Appendix A2

		Smartroof system	Kingspan TEK	Prestoplan PresPeak 60	Wall Cap RDA2	RoofSpace I-Roof	Space4 system	Donaldson Timber Single Leaf Spandrel	NTSROOF RAPID FIT SYSTEM	Lightweight external cladding systems	Nu-Span Spantherm
Timber walls	E-WT-1	~	~	~	~	~		~	~	~	✓
	E-WT-2		~	~	~	~	~	~	~	~	~
	E-WT-3	~			~	~					~
	E-WT-4	/			~	~					~
Steel	E-WS-	1				~					~
walls	E-WS-2	2									
	E-WS-	3									
	E-WS-4	1			~						~
	E-WS-	5									

7. Roof junction – pitched roof without room-in-roof



Alternative detail with single spandrel panel



Junction between separating wall and roof filled with flexible closer

RoofSpace I-Roof[™] spandrel panel lined with 2 layers of 8 kg/m² gypsum board, or 1 layer 15mm Fermacell

External wall cavity closed at eaves level with a suitable flexible material (e.g. mineral wool). If a rigid material is used, then it should only be bonded to one leaf

Continuous horizontal ribbon of adhesive

Wall plate bedded on min. 2mm thin-joint mortar

Spandrel panels to be bedded on flexible sealant or mineral wool strips

100mm (min) mineral wool insulation – 10 kg/m³ (min)

Continuous horizontal ribbon of adhesive

100mm mineral wool max. 40 kg/m³ (no gaps to remain)

Junction between separating wall and roof filled with flexible closer

RoofSpace I-Roof[™] spandrel panel lined with 2 layers of 8 kg/m² gypsum board, or 1 layer 15mm Fermacell

External wall cavity closed at eaves level with a suitable flexible material (e.g. mineral wool). If a rigid material is used, then it should only be bonded to one leaf

Spandrel panels to be bedded on flexible sealant or mineral wool strips

Wall plate bedded on min. 2mm thin-joint mortar

Continuous horizontal ribbon of adhesive

100mm (min) mineral wool insulation – 10 kg/m³ (min)

Cavity closer

Continuous horizontal ribbon of adhesive

100mm mineral wool max. 40 kg/m³ (no gaps to remain)

robustdetails[®]

Edition 4 April 2022 Update This guidance relates only to specific aspects of Part E (England & Wales) & Part G (Northern Ireland) 5 of 8

RoofSpace I-Roof[™] spandrel panel lined with 2 layers of 8 kg/m² gypsum board, or 1 layer 15mm Fermacell External wall cavity closed at eaves level with a suitable flexible material (e.g. mineral wool). If a rigid material is used, then it should only be bonded to one leaf 100mm (min) mineral wool insulation – 10 kg/m³ (min) Continuous horizontal ribbon of adhesive Spandrel panels to be bedded on flexible sealant

8. Stepped roof junction - pitched roof without room-in-roof

00

0

0

, o ,

000

• •

100mm (min)

000

0

Section

or mineral wool strips

Wall plate bedded on min. 2mm thin-joint mortar

Cavity closer

Continuous horizontal ribbon of adhesive

100mm mineral wool max. 40 kg/m³ (no gaps to remain)

Plan

Plan

10.1 – electrical sockets, switches, etc.

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose electrical boxes

Alternatively, fire resistant putty pads or other proprietary liner may be used with sockets, provided:

- a) They achieve a laboratory performance of no worse than rd∆R_w+C_{tr} = -1dB See Appendix H.
- b) They are installed in accordance with the manufacturer's instructions.

Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays

Alternatively provide a service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen.

Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

10.2 – piped services

Service duct within separating wall

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose pipes

Stagger services on each side of wall such that they are not positioned in opposite bays

Note: this detail is not applicable for SVPs or gas pipes.

robustdetails[®]

This guidance relates only to specific aspects of Part E (England & Wales) & Part G (Northern Ireland)

Plan

CHECKLIST (to be completed by site manager/supervisor)

Corr	ipany:			
Site:				
Plot:		Site manager/supervisor:		
Ref.	Item		Yes No (✔) (✔)	Inspected (initials & date)
•	Are wall linings at le	east 240mm apart?	(/) (/)	(Initials & date)
•	Is absorbent mater	ial at least 60mm thick?		
•	Does absorbent ma above ceiling line ir	aterial cover whole lining area except n roof void zone?		
-	Are all joints in wall	lining staggered?		
•	Is separating wall li both sides?	ning correct mass per unit area on		
	Are all joints sealed	I with tape or caulked with sealant?		
-	Are services installe 10.1 and 10.2?	ed in accordance with sketches		
5.	If there is a separat resilient flanking str	ing floor (e.g. in flats/apartments) has th ip been provided?	ne	
-	Is separating wall s	atisfactorily complete?		
Not	t es (include details c	of any corrective action)		
Site	manager/superviso	r signature		

® UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Plan

Plan

9.1 – electrical sockets, switches, etc.

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose electrical boxes

Alternatively, fire resistant putty pads or other proprietary liner may be used with sockets, provided:

- a) They achieve a laboratory performance of no worse than rd∆R_w+C_{tr} = -1dB See Appendix H.
- b) They are installed in accordance with the manufacturer's instructions.

Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays

Alternatively provide a service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen.

Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

9.2 – piped services

Service duct within separating wall

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose pipes

Stagger services on each side of wall such that they are not positioned in opposite bays

robustdetails[®]

Note: this detail is not applicable for SVPs or gas pipes.



(

This guidance relates only to specific aspects of Part E (England & Wales) & Part G (Northern Ireland)

Plan

CHECKLIST (to be completed by site manager/supervisor)

npany:		
Site manager/supervisor:		
Item	Yes No	
Are wall linings at least 240mm apart?		(initials & date)
Are sheathing boards at least 50mm apart?		
Are stud frames at least 68mm apart?		
Is absorbent material at least 60mm thick?		
Does absorbent material cover whole lining area except above ceiling line in roof void zone?		
Are all joints in wall lining staggered?		
Is separating wall lining correct mass per unit area on both sides?		
Are all joints sealed with tape or caulked with sealant?		
Are services installed in accordance with sketches 9.1 and 9.2?		
If there is a separating floor (e.g. in flats/apartments) has the resilient flanking strip been provided?		
Is separating wall satisfactorily complete?		
tes (include details of any corrective action)		
	Site manager/supervisor: Item Are wall linings at least 240mm apart? Are sheathing boards at least 50mm apart? Are stud frames at least 68mm apart? Is absorbent material at least 60mm thick? Does absorbent material cover whole lining area except above ceiling line in roof void zone? Are all joints in wall lining staggered? Is separating wall lining correct mass per unit area on both sides? Are all joints sealed with tape or caulked with sealant? Are services installed in accordance with sketches 9.1 and 9.2? If there is a separating floor (e.g. in flats/apartments) has the resilient flanking strip been provided? Is separating wall satisfactorily complete?	Site manager/supervisor: Item Yes No Are wall linings at least 240mm apart?

® UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Site manager/supervisor signature


Separating Wall – Timber Frame

E-WT-3


Openwall prefabricated panels

Twin timber frames


For use in timber frame houses and flats/apartments



1. External (flanking) wall junction




2. Staggered external (flanking) wall junction




robustdetails[®]


3. Internal floor junction



4. Internal wall junction



5. Ground floor junction: timber floor, beam and block, precast concrete plank, cast in-situ concrete suspended slab or ground bearing slab




Ground floors not continuous between dwellings

Flexible or acoustic sealant (may be omitted when timber ground floor is used)


Ground floor construction:

- timber floor joists:
 - may span in either direction
 - floor decking may run under sole plates
 - close spaces between floor joists with full depth timber blocking where joists are at right angles to wall, or
- beam and block floor with all voids filled with mortar, or
- precast concrete planks with all voids between planks and blockwork filled with mortar or flexible sealant, or
- cast in-situ concrete suspended slab, or
- ground bearing slab

6. Raft foundation



7. Roof junction - pitched roof with no room-in-roof



Junction between separating wall and roof filled

Cavity separating wall continuous to underside

Wall lining above ceiling - 2 or more layers of gypsum-based board (minimum total nominal mass per unit area 16 kg/m²), both sides, all

Absorbent material not required in separating

Alternatively use spandrel panel - see Appendix A

External wall cavity closed at eaves level with a suitable flexible material (e.g. mineral wool). If a rigid material is used, then it should only be

100mm (min) mineral wool insulation, 10 kg/m³ (min), between ceiling joists

Seal all perimeter joints with tape or caulk with sealant

8.1 – electrical sockets, switches, etc.

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose electrical boxes

Alternatively, fire resistant putty pads or other proprietary liner may be used with sockets, provided:

- a) They achieve a laboratory performance of no worse than rd∆R_w+C_{tr} = -1dB
 See Appendix H.
- b) They are installed in accordance with the manufacturer's instructions.

Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays

Alternatively provide a service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen.

Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

8.2 – piped services

Service duct within separating wall

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose pipes

Stagger services on each side of wall such that they are not positioned in opposite bays

Note: this detail is not applicable for SVPs or gas pipes.

Plan

Plan

Plan

blank page See overleaf for checklist



CHECKLIST (to be completed by site manager/supervisor)

lot:		Site manager/supervisor:			
Ref.	Item		Yes (✔)	No (✔)	Inspected (initials & date)
•	Are Openwall panels	being used?			
<u>)</u>	Are wall linings at lea	st 240mm apart?			
3.	Is absorbent material separating wall?	at least 60mm thick in both leaves of the			
I .	Does absorbent mate above ceiling line in r	erial cover whole lining area except roof void zone?			
5.	Are all joints in wall li	ning staggered?			
) .	Is separating wall lini both sides?	ng correct mass per unit area on			
7.	Are all joints sealed w	vith tape or caulked with sealant?			
3.	Are services installed	in accordance with sketches 8.1 and 8.2?			
€.	Is inner leaf lined with minimum density 32	n 45mm (min) foil faced PIR insulation, kg/m ³ ?			
10.	Is separating wall sat	isfactorily complete?			

Notes (include details of any corrective action)


Site manager/supervisor signature

® UK registered trade mark no. 2291665


© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.


7. Raft foundation



8. Roof junction - pitched roof with no room-in-roof







9.1 – electrical sockets, switches, etc.

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose electrical boxes

Alternatively, fire resistant putty pads or other proprietary liner may be used with sockets, provided:

- a) They achieve a laboratory performance of no worse than $rd\Delta R_w+C_{tr} = -1dB$ See Appendix H.
- b) They are installed in accordance with the manufacturer's instructions.

Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays

Alternatively provide a service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen.

Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

9.2 – piped services


Service duct within separating wall

Provide two or more layers of gypsum-based board (total nominal mass per unit area 22 kg/m²) to enclose pipes

Stagger services on each side of wall such that they are not positioned in opposite bays


Note: this detail is not applicable for SVPs or gas pipes.

7. Raft foundation



Below screed insulation, isolating screed from raft Polyethylene

8. Roof junction - pitched roof with no room-in-roof



Junction between separating wall and roof filled with flexible closer.


Cavity separating wall continuous to underside of roof


Wall lining above ceiling – 2 or more layers of gypsum-based board (minimum total nominal mass per unit area 16 kg/m²), both sides, all joints staggered

External wall cavity closed at eaves level with a suitable flexible material (e.g. mineral wool). If a rigid material is used, then it should only be bonded to one leaf

100mm (min) mineral wool insulation, 10 kg/m 3 (min), between ceiling joists

Seal all perimeter joints with tape or caulk with sealant





Edition 4 April 2022 Update This guidance relates only to specific aspects of Part E (England & Wales) & Part G (Northern Ireland) 7 of 8

CHECKLIST (to be completed by site manager/supervisor)

Plot:		Site manager/supervisor:		
Ref.	Item		Yes No	
1.	Are wall linings at le	ast 190mm apart?	(v) (v) (initials & date)
2.		al 100mm (min) Isover nin density 10 kg/m³)?		
3.	Is quilt compressed	between studs?		
4.		ning two layers of 15mm plasterboard on both sides?		
5.	Are all joints in wall	lining staggered?		
6.	Are all joints sealed	with tape or caulked with sealant?		
7.	Are services and soc 10.1 and 10.2?	ckets installed in accordance with sketches		
8.	Is separating wall sa	atisfactorily complete?		
Cor	ntact details for technical	assistance from British Gypsum, manufacturer of G	iypwall QUIE	Γ IWL steel frames:
Tel	ephone: 0844 800 19	91 Fax: 0844 561 8816 E-mail: bgt	echnical.er	iquiries@bpb.com

Site manager/supervisor signature


® UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.


Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

E-WS-5

9. Ground floor junction



10. Internal wall junction




Plan

Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames



11.1 Electrical sockets, switches etc



Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays

Provide two or more layers of gypsum-based board (total nominal mass per unit area 20 kg/m²) to enclose electrical boxes

Alternatively, fire resistant putty pads or other proprietary liner may be used with sockets, provided:

- a) They achieve a laboratory performance of no worse than $rd\Delta R_w + C_{tr} = -1dB$ See Appendix H.
- b) They are installed in accordance with the manufacturer's instructions.

Fire resistant seal where required by Part B of the Building Regulations

Service void using min 25mm battens or steel studs with 1 layer of gypsum board

Service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen


Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

Provide two or more layers of gypsum-based board (total nominal mass per unit area 20 kg/m²) to enclose pipes

Stagger services on each side of the wall such that they are not positioned in opposite bays


Note: this detail is not applicable for SVPs or gas pipes

11.2 Electrical sockets and switches in service void



Plan

11.3 Piped services located within wall



Plan

Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

Contents

Section	⊃age
Icopal-MONARFLOOR [®] BRIDGESTOP [®] System for robustdetails [®] masonry cavity walls	2
Smartroof complete Interlocking "room-in-roof" panel system using robustdetails® timber or masonry cavity walls	3
Kingspan TEK inner leaf flanking condition for robust details [®] timber separating walls	4
Prestoplan PresPeak 60 interlocking single spandrel panel system for robust details® timber separating walls	5
Icopal-MONARFLOOR [®] Wall Cap RDA2 System for robust details [®] separating floors with cavity flanking walls	6
RoofSpace I-Roof™ "room-in-roof" panel system using robustdetails® timber or masonry cavity walls	7
Space4 "room-in-roof" panel system using robustdetails [®] timber or masonry cavity walls	8
Donaldson Timber Systems Single Leaf Spandrel Panel System for robust details® timber separating walls	9
NTS ROOF <i>RAPID FIT SYSTEM</i> for robust details [®] timber or masonry cavity walls	10
Lightweight external cladding for robust details® timber separating walls	11
Flanking construction to robust details® precast concrete separating floors around private stairs	12
Nu-Span and Spantherm pre-insulated ground floor concrete slabs for use on robust details® cavity separating walls	16

b

С

е

Icopal-MONARFLOOR® BRIDGESTOP® System for robust details® cavity masonry walls. Refer to Table 6 in Introduction.


1. Separating wall - direct support on raft а 3 b С 2 1 4 5 е

3. Insulated raft foundation

3

2

2. Separating wall - suspended floor with gas membrane а 3 b С 2 1 5




- Key
- 1 500mm wide (or 250mm where shown) MONARFLOOR® BRIDGESTOP® 3mm HP Acoustic Membrane laid under the party wall over the dpm. This is an integral part of the system.
- 2 MONARFLOOR® BRIDGESTOP® Quilt in two lifts to prevent mortar droppings touching both masonry leaves.
- 3 MONARFLOOR® BRIDGESTOP® Tie to penetrate at max 450mm centres. Ties are reversible. May also be used as render depth marker.
- 4 MONARFLOOR® 6mm Flanking Band forming a 90° angle to isolate floating floor treatment from separating wall blocks, lining and skirting board.
- 5 Continuous dpm over the raft where ground gasses are an issue. Contact Icopal for specification.

- a Min 100mm block (with appropriate Type A wall ties) dependent on Robust Detail being used. Refer to Table 6a in the Introduction.
- b Min 75mm or 100mm cavity width dependent on Robust Detail being used.
- c Wall finish dependent on Robust Detail used.
- d Floating screed on insulation; or timber floating floor types FFT2 resilient cradle and batten, FFT3 resilient batten, or FFT4 deep platform system.
- e 150mm (min) thick insitu concrete 365kg/m² (min) mass per unit area or Insulslab SFRC.

Contact details for Icopal-MONARFLOOR®: Telephone: 0161 866 6540 Fax: 0161 865 8433 E-mail: acoustics.uk@icopal.com

The trade marks MONARFLOOR and BRIDGESTOP are the subject of UK trade mark registrations owned by Icopal Limited


BRIDGESTOP® is the subject of Patent Application ref GB2429719




Donaldson Timber Systems Single Leaf Spandrel Panel System for use on **robust**details[®] timber separating walls in non room-in-roof situations. Refer to Table 6 in Introduction.


1. Spandrel panel located parallel to trussed rafters

2. Spandrel panel located across trussed rafters





3. Spandrel panel joint detail Panels secured together using angled screw fixings



Key

- 1 Donaldson Timber Systems Single Leaf Spandrel Panel System.
- a Mineral wool closer.
- b Flexible cavity stop.
- c Timber frame separating wall.
- d Site-fixed runners must not contact both wall leafs.
- e Angled screw fixings to secure spandrel to wall head.
- f Trusses and rafters must not contact both wall leafs.
- g Gypsum board cover strip.

Refer also to manufacturer's guidance


Contact details for Donaldson Timber Systems Limited:

Telephone: 0845 009 2774 Email: help@donaldsontimbersystems.com Web: www.donaldsontimbersystems.com




9

NTSROOF *RAPID FIT SYSTEM* for **robust**details[®] timber or masonry cavity walls for "room-in-roof" situations. Refer to Table 6 in Introduction.




1. Room-in-roof junction with timber cavity walls

2. Room-in-roof junction with masonry cavity walls




3. Separating wall – roof junction



Key

- a Outer leaf of external wall.
- b Timber robust details® wall (see Table 6 in Introduction).
- c Blockwork dependent on Robust Detail used.
- d Intumescent sealant.
- e Cavity insulation dependent on Robust Detail used.
- f Gypsum-based board (nominal 10 kg/m²).
- g Gypsum-based board (nominal 8 kg/m²)
- h Min. 1 layer gypsum-based board (nominal 10 kg/m²).
- i Vertical metal straps if required. Straps must not extend into the cavity.
- j Wall plate bedded on mortar, notched to take straps.
- k Cavity closer if required for other Regulations.

4. Room-in-roof lining requirements



- 1 NTSROOF spandrel panel.
- 2 NTSROOF roof cassette.

Contact details for National Timber Systems:

Telephone: 01609 751111 Fax: 01609 788388 E-mail: george.rayden@nationaltimbersystems.co.uk Web: www.nationaltimbersystems.co.uk

robustoetails® This guidance relates only to specific aspects of Part E (England & Wales) & Part G (Northern Ireland)

Edition 4 April 2022 Update